



ಬೆಂಗಳೂರು ನೀರು ಸರಬರಾಜು ಮತ್ತು ಒಳಚರಂಡಿ ಮಂಡಳಿ  
ಮುಖ್ಯ ಅಭಿಯಂತರರು (ವಿನ್ಯಾಸ & ಗುಣ ಆಶ್ವಾಸನೆ) ರವರ ಕಛೇರಿ  
9ನೇ ಮಹಡಿ, ಕಾವೇರಿ ಭವನ, ಕೆಂಪೇಗೌಡ ರಸ್ತೆ, ಬೆಂಗಳೂರು-560009.

ದೂರವಾಣಿ: 080-22945340

ಇ-ಮೇಲ್: [cedesign@bwssb.gov.in](mailto:cedesign@bwssb.gov.in)

No: BWSSB/CE(D&QA)TE/ACE/TA/ 5a /2024-25 Date: 22/04/2024

ಸೇರ್ಪಡೆ ಹಾಗೂ ತಿದ್ದುಪಡಿ ಜ್ಞಾಪನಾ ಪತ್ರ

**(CSR 2023-24 Vol-5 Addendum-1/2024-25 & Corrigendum-1/2024-25)**

ವಿಷಯ: 2023-24 ನೇ ಸಾಲಿನ ನೀರು ಸರಬರಾಜು ಮತ್ತು ಒಳಚರಂಡಿ ಕಾಮಗಾರಿಗಳ ಏಕರೂಪ ಅನುಸೂಚಿ ದರಪಟ್ಟಿ ಸಂಪುಟ-5 ರಲ್ಲಿ ಹೆಚ್ಚುವರಿ ಅಂಶಗಳ ಸೇರ್ಪಡೆ ಮತ್ತು ತಿದ್ದುಪಡಿ ಕುರಿತು.

- ಉಲ್ಲೇಖ: 1) ಸ.ಆ.ಸಂ.ನ.ಅ.ಇ08/ಐಎನ್‌ಐ2021 (ಇ-ಕಛೇರಿ), ಬೆಂಗಳೂರು  
ದಿನಾಂಕ: 04.12.2021.  
2) ಸರ್ಕಾರದ ಆದೇಶ ಸಂಖ್ಯೆ: ಲೋ.ಇ 86 ಆರ್‌ಡಿಎಫ್ 2022, ಬೆಂಗಳೂರು  
ದಿನಾಂಕ: 15.11.2023.  
3) ದಿನಾಂಕ: 06.04.2024 ರಂದು ನಡೆದ ಖಾಯಂ ನಿರತ ಏಕರೂಪ ದರಪಟ್ಟಿ ತಯಾರಿಕಾ ಸಮಿತಿಯ 2024-25 ನೇ ಸಾಲಿನ 2ನೇ ಸಭೆಯ ನಡವಳಿಗಳು.

\*\*\*\*\*

**ಪ್ರಸ್ತಾವನೆ:**

ಮೇಲಿನ ವಿಷಯಕ್ಕೆ ಸಂಬಂಧಿಸಿದಂತೆ, ಉಲ್ಲೇಖ (2) ರ ಸರ್ಕಾರದ ಆದೇಶದನ್ವಯ ನೀರು ಸರಬರಾಜು ಮತ್ತು ಒಳಚರಂಡಿ ಕಾಮಗಾರಿಗಳ ಏಕರೂಪ ಅನುಸೂಚಿ ದರಪಟ್ಟಿ: 2023-24 ನ್ನು ದಿನಾಂಕ: 15.11.2023 ರಿಂದ ಜಾರಿಗೆ ಬರುವಂತೆ ಅಳವಡಿಕೆಗೆ ಪ್ರಕಟಿಸಲಾಗಿತ್ತು. ಸದರಿ 2023-24ನೇ ಸಾಲಿನ ಏಕರೂಪ ಅನುಸೂಚಿ ದರಪಟ್ಟಿ (ಸಂಪುಟ-5) ಅನ್ನು 2024-25ನೇ ಆರ್ಥಿಕ ವರ್ಷದ ಸಾಲಿಗೆ ಅನ್ವಯಿಸುವಂತೆ ಮುಂದಿನ ಆದೇಶದವರೆಗೆ ಮುಂದುವರೆಸಲು ಆದೇಶಿಸಲಾಗಿರುತ್ತದೆ.

ಸದರಿ ದರಪಟ್ಟಿಯಲ್ಲಿ ಕೆಲವು ಹೆಚ್ಚುವರಿ ಅಂಶಗಳ ಸೇರ್ಪಡೆ ಮತ್ತು ತಿದ್ದುಪಡಿಯ ಅವಶ್ಯಕತೆ ಕಂಡುಬಂದ ಹಿನ್ನೆಲೆಯಲ್ಲಿ ಉಲ್ಲೇಖ (1) ರ ಆದೇಶದನ್ವಯ ರಚಿತವಾಗಿರುವ ಬೆಂಗಳೂರು ನೀರು ಸರಬರಾಜು ಮತ್ತು ಒಳಚರಂಡಿ ಮಂಡಳಿ, ಕರ್ನಾಟಕ ನಗರ ನೀರು ಸರಬರಾಜು ಮತ್ತು ಒಳಚರಂಡಿ ಮಂಡಳಿ, ಗ್ರಾಮೀಣ ಕುಡಿಯುವ ನೀರು ಮತ್ತು ನೈರ್ಮಲ್ಯ ಇಲಾಖೆಗಳನ್ನೊಳಗೊಂಡ ನೀರು ಸರಬರಾಜು ಮತ್ತು ಒಳಚರಂಡಿ ಕಾಮಗಾರಿಗಳ ಏಕರೂಪ ದರಪಟ್ಟಿಯ ತಯಾರಿಕಾ ಖಾಯಂ ಸಮಿತಿಯು ಸಭೆ ಸೇರಿ ಸಂಪುಟ-5 ಕ್ಕೆ ಜಲ ಜೀವನ್ ಮಿಷನ್ ಯೋಜನೆಯ ಕಾಮಗಾರಿಗಳ ನಾಮಫಲಕದ ಅಂಶಗಳು ಮತ್ತು ಕೊಳವೆಬಾವಿ ಕೊರೆಯುವ/ಮರು ಕೊರೆಯುವ ಕಾಮಗಾರಿಗಳ ಉಪಯುಕ್ತ ಅಂಶಗಳನ್ನು ಸೇರ್ಪಡೆಗೊಳಿಸಲು, ಪಿ.ವಿ.ಸಿ ಕೊಳವೆಗಳ ಅಂಶಗಳಲ್ಲಿನ ವಿಶಿಷ್ಟ ವಿವರಣೆಯ ತಿದ್ದುಪಡಿಗೆ ಹಾಗೂ Conveyance Charges for DI/CI Pipes ಅಂಶಗಳನ್ನು ತೆಗೆದು ಹಾಕುವ ಬಗ್ಗೆ ಕೂಲಂಕಷವಾಗಿ ಚರ್ಚಿಸಿ ಅಗತ್ಯ ಪ್ರಕಟಣೆ ಹೊರಡಿಸಲು ತೀರ್ಮಾನಿಸಲಾಯಿತು.

'ವಿನ್ಯಾಸ' ಎಂಬುದು ದೃಶ್ಯೀಕರಿಸಿದ ಆಲೋಚನೆ.

ಪುಟ ಸಂಖ್ಯೆ 1 of 5


C.E. (D & QA)  
BWSSB

**ಆದೇಶ:**

ನೀರು ಸರಬರಾಜು ಮತ್ತು ಒಳಚರಂಡಿ ಕಾಮಗಾರಿಗಳ ಏಕರೂಪ ದರಪಟ್ಟಿಯ ತಯಾರಿಕೆ ಖಾಯಂ ಸಮಿತಿಯ ಉಲ್ಲೇಖ-3 ರಲ್ಲಿನ ಸಭೆಯಲ್ಲಿ ಮೇಲಿನ ಅಂಶಗಳನ್ನು ಪರಿಶೀಲಿಸಿ, ಸಮಿತಿಯ ಅಭಿಪ್ರಾಯದಂತೆ ಸಂಪುಟ-5 ರ ದರಪಟ್ಟಿಗೆ ಅವಶ್ಯವಿರುವ ಹೆಚ್ಚುವರಿ ಹೊಸ ಅಂಶಗಳ ಸೇರ್ಪಡೆಯನ್ನು Addendum-1/2024-25 ಹಾಗೂ ಸೂಕ್ತ ತಿದ್ದುಪಡಿಗಳನ್ನು Corrigendum-1/2024-25 ರಲ್ಲಿ ರಾಜ್ಯ ವ್ಯಾಪ್ತಿ ನೀರು ಸರಬರಾಜು ಮತ್ತು ಒಳಚರಂಡಿ ಕಾಮಗಾರಿಗಳನ್ನು ಕೈಗೊಳ್ಳುವ ಎಲ್ಲಾ ಇಲಾಖೆ/ಸಂಸ್ಥೆಗಳಿಗೆ ದಿನಾಂಕ:22.04.2024 ರಿಂದ ಅನ್ವಯಿಸುವಂತೆ ಆದೇಶಿಸಲಾಗಿದೆ ಹಾಗೂ ಬೆಂಗಳೂರು ಜಲಮಂಡಳಿಯ ಅಧಿಕೃತ ಜಾಲತಾಣವಾದ [www.bwssb.karnataka.gov.in](http://www.bwssb.karnataka.gov.in) ರಲ್ಲಿ ಪ್ರಕಟಿಸಲಾಗಿದೆ.

**ಅಡಕ: 1) Addendum-1/2024-25**

**2) Corrigendum-1/2024-25**

  
ಮುಖ್ಯ ಅಭಿಯಂತರರು (ವಿನ್ಯಾಸ & ಗುಣ ಆಶ್ವಾಸನೆ)  
ಬೆಂಗಳೂರು ನೀರು ಸರಬರಾಜು ಮತ್ತು ಒಳಚರಂಡಿ ಮಂಡಳಿ  
ಹಾಗೂ ಅಧ್ಯಕ್ಷರು, ನೀರು ಸರಬರಾಜು ಮತ್ತು ಒಳಚರಂಡಿ  
ಕಾಮಗಾರಿಗಳ ಏಕರೂಪ ದರಪಟ್ಟಿ ಸಮಿತಿ

**ಪ್ರತಿಯನ್ನು:**

1. ಸರ್ಕಾರದ ಅಪರ ಮುಖ್ಯ ಕಾರ್ಯದರ್ಶಿಗಳು, ಲೋಕೋಪಯೋಗಿ ಇಲಾಖೆ ಹಾಗೂ ಅಧ್ಯಕ್ಷರು, ಅನುಸೂಚಿ ದರಗಳ ಪರಿಶೀಲನಾ ಸಮಿತಿ ರವರ ಘನ ಮಾಹಿತಿಗಾಗಿ.
2. ಸರ್ಕಾರದ ಕಾರ್ಯದರ್ಶಿಗಳು, ಲೋಕೋಪಯೋಗಿ ಇಲಾಖೆ ಹಾಗೂ ಅಧ್ಯಕ್ಷರು, ಅನುಸೂಚಿ ದರಗಳ ರಚನಾ ಸಮಿತಿ ರವರ ಘನ ಮಾಹಿತಿಗಾಗಿ.
3. ಅಧ್ಯಕ್ಷರು, ಬೆಂಗಳೂರು ನೀರು ಸರಬರಾಜು ಮತ್ತು ಒಳಚರಂಡಿ ಮಂಡಳಿ/ ವ್ಯವಸ್ಥಾಪಕ ನಿರ್ದೇಶಕರು, ಕರ್ನಾಟಕ ನಗರ ನೀರು ಸರಬರಾಜು ಮತ್ತು ಒಳಚರಂಡಿ ಮಂಡಳಿ, ಬೆಂಗಳೂರು / ಆಯುಕ್ತರು, ಗ್ರಾಮೀಣ ಕುಡಿಯುವ ನೀರು ಮತ್ತು ನೈರ್ಮಲ್ಯ ಇಲಾಖೆ, ಬೆಂಗಳೂರು, ರವರ ಘನ ಮಾಹಿತಿಗಾಗಿ.
4. ಸರ್ಕಾರದ ಕಾರ್ಯದರ್ಶಿಗಳು, ಆರ್ಥಿಕ ಇಲಾಖೆ (ವೆಚ್ಚ), ಬೆಂಗಳೂರು ರವರ ಘನ ಮಾಹಿತಿಗಾಗಿ.
5. ಅಧ್ಯಕ್ಷರು, ಏಕರೂಪ ಅನುಸೂಚಿ ದರಪಟ್ಟಿ ತಾಂತ್ರಿಕ ಕಾರ್ಯಪಡೆ, ಬೆಂಗಳೂರು ರವರ ಘನ ಮಾಹಿತಿಗಾಗಿ.
6. ಪ್ರಧಾನ ಅಭಿಯಂತರರು/ಮುಖ್ಯ ಅಭಿಯಂತರರು BWSSB, KUWS&DB and RDW&SD ಹಾಗೂ ಸರ್ಕಾರದ ಇತರ ಇಲಾಖೆ / ನಿಗಮ /ಮಂಡಳಿ ರವರ ಮಾಹಿತಿಗಾಗಿ.
7. ಸಮಿತಿಯ ಸದಸ್ಯರು, ಏಕರೂಪ ಅನುಸೂಚಿ ದರಪಟ್ಟಿ ಸಂಪುಟ-5 ರವರ ಮಾಹಿತಿಗಾಗಿ.
8. ಸರ್ಕಾರದ ಎಲ್ಲಾ ಇಲಾಖೆ/ನಿಗಮ ಮಂಡಳಿಗಳ ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು / ಅಪರ ಮುಖ್ಯ ಅಭಿಯಂತರರು ಹಾಗೂ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರ ಮಾಹಿತಿಗಾಗಿ (ವೆಬ್‌ಸೈಟ್ ಮುಖಾಂತರ)
9. ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು (ಎಂ.ಐ.ಎಸ್), ಬೆಂಗಳೂರು ಜಲಮಂಡಳಿ ರವರ ಗಮನಕ್ಕಾಗಿ ಹಾಗೂ ಅಧಿಕೃತ ಜಾಲತಾಣದಲ್ಲಿ ಪ್ರಕಟಿಸಲು.
10. ಕಛೇರಿ ಕಡತಕ್ಕಾಗಿ.

**1st Addendum/2024-25**  
**COMMON SCHEDULE OF RATES 2023-24 VOLUME-V**  
**WATER SUPPLY AND SEWERAGE WORKS**  
**With effect from 22.04.2024**

**Based on the inputs/suggestions/ requests received from Committee Officers & Engineers, the following Addendum has been issued.**

**Chapter-13: SUBMERSIBLE PUMPSETS AND REPLACEMENT OF PARTS**

Sl. NO	Specification	UNIT	RATE (in Rs.)
13.89	Providing, lowering and jointing 40mm dia 25 gauge HDPE pipes of specified grade and conveying to work site including loading and unloading at both destinations and rolling and lowering into Borewell, inclusive of required specials and SS fittings wherever necessary etc.	m	190
13.90	Providing, lowering and jointing 50mm dia 25 gauge HDPE pipes of specified grade and conveying to work site including loading and unloading at both destinations and rolling and lowering into Borewell, inclusive of required specials and SS fittings wherever necessary etc.	m	290
13.91	Providing, lowering and jointing of 5 inch dia 6 gauge slotted PVC pipe of specified grade and conveying to work site including loading and unloading at both destinations and rolling and lowering into Borewell, inclusive of required specials and SS fittings whenever necessary etc, complete.	m	849
13.92	Providing Submersible Pump Set of 150mm dia suitable for borewell and confirming to IS 8034-2000; 3Phase, SS Bowl & Impeller with Low volt Motor as per specifications, to work site as per necessary amendments and instructions of Engineer in charge of work.		
13.92.1	12.5 HP 30 Stage	Each	94892
13.92.2	15 HP 35 Stage	Each	105775
13.92.3	17.5 HP 30 Stage	Each	108165
13.92.4	17.5 HP 35 Stage	Each	111293
13.92.5	17.5 HP 40 Stage	Each	116459
13.92.6	17.5 HP 45 Stage	Each	123429
13.92.7	20 HP 30 Stage	Each	111328
13.92.8	20 HP 40 Stage	Each	120126
13.92.9	20 HP 50 Stage	Each	132157
13.93	Providing Submersible Pumpset of 100mm dia suitable for borewell and confirming to IS 8034-2000; 3Phase, SS Bowl & Impeller with Low volt Motor as per specifications, to work site as per necessary amendments and instructions of Engineer in charge of work.		
13.93.1	5 HP 40 Stage	Each	60731
13.93.2	5 HP 52 Stage	Each	69306
13.93.3	6 HP 52 Stage	Each	71309
13.93.4	6 HP 62 Stage	Each	78889
13.93.5	7.5 HP 60 Stage	Each	80189
13.93.6	7.5 HP 77 Stage	Each	92959
13.93.7	7.5 HP 80 Stage	Each	95161
13.93.8	10 HP 50 Stage	Each	101229
13.93.9	10 HP 80 Stage	Each	103584
13.93.10	10 HP 100 Stage	Each	130611

**Chapter-23: MISCELLANEOUS ITEMS  
(New Chapter)**

23.1	<p>Providing and fixing of typical 'Information Board' as per specifications and drawing with respect to the guidelines of scheme including relevant details of the scheme, logo, total cost of schemes, implementing agency/vendor, names &amp; contacts of EE/JE Paani Samiti Chairperson &amp; Secretary, commencement &amp; completion date etc.,.The board consists of ACP Sheet of 4mm thickness having minimum 0.25mm thick aluminum skin both sides and fixed over a back support of MS plate 75mmx 5mm thick. Supported on frame post of 2 no's of MS tube 14 guage 75mm dia which is duly embedded in cement concrete M20 Grade of 600x600x750mm,750mm below ground level. All MS will be stove enameled on both the sides. All sections of framed posts, MS sheet and Stell tubes will be painted with primer and two coats of epoxy paint as per drawing etc.. Retro-Reflective Sheet as per IRC 67 fixed over an Aluminum Composite Material(ACP) sheeting of size 2.45X1.8m (8'x6') of 4mm thickness duly bolted/riveted with MS plate of 5mm thickness on backside of ACP Sheet including cost and conveyance of all materials,equipment,machinery and labour with all leads and lifts, loading charges, charges necessary for satisfactory completion of work as directed by Engineer incharge.</p> <p>(i) For warranty and durability the clause 1701.5 and for maintenance the clause 1911 shall be applicable.</p> <p>(ii) A reference number along with the month and year of installation should be placed on the back of sign Board in a contrasting colour or by stamping in characters 485777/2019/Dir(Tech) 7.</p>	Job	33902
23.2	<p>Providing and fixing of typical 'Information Board' as per specifications and drawing with respect to the guidelines of scheme including relevant details of the scheme, logo, total cost of schemes, implementing agency/vendor, names &amp; contacts of EE/JE Paani Samiti Chairperson &amp; Secretary, commencement &amp; completion date etc.,.The board consists of MS Sheet of 3mm thickness fixed over a back support of MS equal angles 50mm x 50mm x 5mm thick. Supported on frame post of 2 no's of MS square hollow section 14 guage 75mm dia which is duly embedded in cement concrete M20 Grade of 600 x 600 x 750mm, 750mm below ground level. All MS will be stove enameled on both the sides. All sections of framed posts, MS sheet and Stell tubes will be painted with primer and two coats of epoxy paint with preparation of screen, lettering etc., as per drawings including cost &amp; conveyance of all materials, equipment, machinery and labour with all leads and lifts, loading charges, charges necessary for satisfactory completion of work as directed by Engineer incharge.</p> <p>(i) For warranty and durability the clause 1701.5 and for maintenance the clause 1911 shall be applicable.</p> <p>(ii) A reference number along with the month and year of installation should be placed on the back of a sign in a contrasting colour or by stamping in characters.485777/2019/Dir(Tech) 7.</p>	Job	20043

**1st Corrigendum/2024-25**  
**COMMON SCHEDULE OF RATES 2023-24 VOLUME-V**  
**WATER SUPPLY AND SEWERAGE WORKS**  
**With effect from 22.04.2024**

Based on the inputs/suggestions/ requests received from Committee Officers & Engineers, the following Corrigendum has been issued.

SL NO	PAGE NO	Specification as printed in CSR 2023-24 Vol-V	Unit	Rate (in Rs)	CORRECTED/ CLARIFIED AS
<b>Chapter-10: WATER SUPPLY WORKS</b>					
2.16	20	Conveying CI / DI pipes and specials through transporting vehicles like lorry, trucks etc. as detailed complete.			<b>DELETED</b>
2.16.1		Conveyance including loading and unloading per quintal for distance upto 5.00 KM	QNT	150	
2.16.2		Conveyance excluding loading and unloading per quintal for distance 5.00 to 10.00 KM	QNT	26	
2.16.3		Conveyance excluding loading and unloading per quintal for distance beyond 10.00 KM	QNT	16	
<b>Chapter-10: PVC PIPE WORKS</b>					
10.14	120	Providing and installing at site of work P.V.C. pipes including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour charges and all lift charges, handling charges including encasing the pipe around to a depth not less than 15 cms with gravel or selected earth available from the excavation etc. complete.			
10.14.1		4 Kg/m <sup>2</sup>	m	As per latest issue rates.	4 Kg/cm <sup>2</sup>
10.14.8		6 Kg/m <sup>2</sup>	m		6 Kg/cm <sup>2</sup>
10.14.15		8 Kg/m <sup>2</sup>	m		8 Kg/cm <sup>2</sup>
10.14.22		10 Kg/m <sup>2</sup>	m		10 Kg/cm <sup>2</sup>
	121				

*[Signature]*  
**C.E. (D & QA) 2/7/24**  
**BWSSB** 